



Pad #1 - 6'-6" x 5'-8" x 6"

Notes:
 4000 PSI Concrete W/ 5% Air
 Reinforcement - Grade 60
 Inserts - 2 - Dayton Superior Swift Lift Anchors
 P-52SL 4 Ton
 Weight - 2300 Lbs.

Crest Precast, Inc.		
La Crescent, MN & Barneveld, WI		
609 Kistler La Crescent, MN 55947		
Scale		Drawn By: KG
Date	3-7-06	Revision
Project: Transformer Pad #1		
Contractor:		Drawing Number