



Pad #2 - 8'-8" x 8'-4" x 8"

Notes:
 4000 PSI Concrete W/ 5% Air
 Reinforcement - Grade 60
 Inserts - 2 - Dayton Superior Swift Lift Anchors
 P-52SL 4 Ton
 Weight - 6500 Lbs.

Crest Precast, Inc.		
La Crescent, MN & Barneveld, WI		
609 Kistler La Crescent, MN 55947		
Scale		Drawn By: KGT
Date	3-7-06	Revision
Project: Transformer Pad #2		
Contractor:		Drawing Number